

EDAW | AECOM

 **MONASH University**
Engineering
Institute for Sustainable Water Resources

 **FAWB**
Facility for Advancing
Water Biofiltration

Advancing Raingarden Design **Construction**

June 2008



Construction Process

1. Bulk Earthworks
2. Perforated pipe
3. Drainage layer
4. Sandy loam
5. Geofabric
6. Topsoil
7. Turf

When 75% building complete, turf, topsoil and geofabric removed and final planting undertaken



Must protect systems during building phases



Construction activities can impact on maintenance requirements



Protect system during construction and establishment of landscaping features




How to control sediment loads during construction/building?

- Temporary sediment control at entrances
- Replace vegetation at completion of construction/building phase




Protection during construction

-Turf layer





Alternatively use partitioning and sediment control during building phase



- Good for developer
- Good for Council
- Good for residents

Sediment and Erosion Control





Examples of what can go wrong when good designs are poorly constructed



Scouring
Sediment deposition



Blockage by leaf litter



Incorrect grade & levels

Poor finish

Incorrect rock

Incorrect filter media

Lightly compact filter media to avoid over-compaction or future subsidence



Planting & Landscape Elements



Co-ordination and communication are important: mulch netting but no mulch

Planting into compacted filter media

Correct plant species and pot size

Planting too deep

Inspection before handover

Asset Handover Checklist			
<i>Asset Location:</i>			
<i>Construction by:</i>			
<i>Defects and Liability Period</i>			
Treatment		Y	N
Actual treatment performance equivalent to design?			
Maintenance		Y	N
Maintenance plans provided for each asset?			
Inspection and maintenance undertaken as per maintenance plan?			
Inspection and maintenance forms provided?			
Asset inspected for defects?			
Asset Information		Y	N
Design Assessment Checklist provided?			
As constructed plans provided?			
Copies of all required permits (both construction and operational) submitted?			
Proprietary information provided (if applicable)?			
Digital files (eg drawings, survey, models) provided?			
Asset listed on asset register or database?			

CONSTRUCTION TIPS

- ▶ Can be counter-intuitive to contractors
- ▶ Support contractors so they understand what is happening, spend time communicating design intent
- ▶ Recommend site visits by someone who understands functional intent and key points during construction phase
- ▶ Careful construction will result in good performance and minimise future maintenance





Stringybark Creek infiltration

